

**HALFWAY SHOP CONSTRUCTION NOTES**  
**Addendum #1 to the Plans for the Project**  
**March 26, 2020**

All requests for information will go to Baker County, and if needed, we will relay requests of information on to others.

- 1) Completely remove block chimney to concrete floor.
- 2) Remove inside wall plywood around posts to install blocking.
- 3) Must not remove more than half (1/2) of roof structures at one time.
- 4) Replace the section of removed roof before removing additional roof structure for safety.
- 5) Owner is requesting an alternate bid pricing for the addition of installing 5/8" waferwood subsheeting over roof framing and using heavy duty roofing paper (Hybrid Felt #30).
- 6) Replace wood burning flues with new metal approved chimney material two (2) each.